



Sunnyslope Water District

3570 Airline Highway

Phone (831) 637-4670

Hollister, California 95023-9702

Fax (831) 637-1399

BID ADDENDUM NO. 3

BEST ROADS MUTUAL WATER COMPANY WATER SYSTEM
CONSOLIDATION PROJECT, CALIFORNIA DEPARTMENT OF WATER
RESOURCES GRANT AGREEMENT NO 4600015596.

12/26/2024

Approved by:

Rob Hillebrecht, P.E.

Principal Engineer

A handwritten signature in black ink, appearing to read 'Rob Hillebrecht', is positioned below the printed name.

1. Introduction

This addendum forms a part of the contract documents and modifies the original bidding documents issued on November 11, 2024. All bidders must acknowledge receipt of this addendum in their bid submission.

Failure to acknowledge Addendum 3 may be grounds for rejection of a bid.

All bids must be delivered in a sealed envelope by **3:00 PM on Tuesday, January 7, 2025.**

2. Questions from Bidders and Official Answers by Sunnyslope

Written Questions Submitted After Addendum No. 1 Was Issued

No.	Date	Contractor	Question	Answer
1	12/16/2024	Graniterock	Article 7 of the bid form conflicts with Article 29 of the Instructions to Bidders. Can we get clarification as to which forms are due with the bid?	Article 29 from the Instructions to Bidders is correct list of documents required with the Bid. In Article 7, strike “(b) Designation of Equipment or Material Manufacturers” and strike “(f) Bidder’s References”. Those documents were not provided in the bid forms and are not required with this Bid.
2	12/26/2025		Is any of the work at the Foxhill Tank that was talked about in the pre-bid meeting included in the project?	No, contrary to what was described in the pre-bid meeting, there will not be any work done at the Foxhill Tank site.
3	12/26/2025		Is there any ACP pipe at the Well 5 site that must be cut or disposed of?	Yes, based on Sunnyslope’s records the piping at Well 5 transitions from steel to ACP when it goes underground. The section of ACP from where piping currently undergrounds to the new undergrounding and tie in point must be removed and disposed of by the contractor. This supersedes Question 8 of Addendum 1.
4	12/26/2025		How much space may the contractor have at Well 5 to stage equipment and materials?	Sunnyslope needs 24/7 access to the well site and existing equipment including the trailer mounted generator. Contractor may utilize the entire site as long as access is provided for Sunnyslope staff.
5	12/26/2025		How long can Well 5 be off line for the piping work?	Sunnyslope would prefer for the well to be off line for less than 3 weeks for the piping work. Contractor shall coordinate

				with Sunnyslope to minimize the down time.
6	12/26/2025		What testing will be required for Well 5 piping?	Hydrostatic, disinfection, and bacteriological testing are all required of the new piping at Well 5. To accomplish this the contractor shall lay short of the tie in points and install a plate at the well connection. After passing all testing, contractor shall remove the plate and make the final underground connections.